



तुलसीपुर उपमहानगरपालिका

नगर कार्यपालिकाको कार्यालय



पत्रसङ्ख्या :- ०८०/०८१

चलानी नं. :- ४३४२

तुलसीपुर, दाङ
लुम्बिनी प्रदेश, नेपाल

२०७३

दररेट पेश गर्ने सम्बन्धि सुचना ।

प्रथम पटक सुचना प्रकाशित मिति २०८१।०२।२९

यस तुलसीपुर उपमहानगरपालिका द्वारा विभिन्न फर्म संग तपशिल बमोजिमको कार्य गर्नका लागि शिलबन्दी दररेट पेश गर्ने यो सुचना प्रकाशित गरिएको छ ।

सि. नं.	कामको विवरण	जम्मा रकम रु (मु. अ. क. बाहेक)	दररेट पेश गर्ने अन्तिम मिति	कैफियत
१	Simalkanchi Road Gravel & Canal Construction Tulsipur-11	८,८३,५१५।६९	२०८१।०३।०३	

१. दररेट पेश गर्ने फर्मले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोराको लिखित निवेदन सहित नबिकरण भएको फर्म दर्ता प्रमाणपत्रको प्रतिलिपी र आ.व.२०७९।०८० को करचुक्ता प्रमाणपत्रको प्रतिलिपी पेश गर्नु पर्ने छ ।

२. दररेट पेश गर्ने फर्म तुलसीपुर उपमहानगरपालिका कार्यालयमा सुचिकृत हुनुपर्ने छ ।

३. उक्त कार्यको लागि आवश्यक BOQ तुलसीपुर उपमहानगरपालिकाको वेबसाइट <http://www.tulsipurmun.gov.np> बाट डाउनलोड गर्न सकिने छ ।

४. BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि लेखेर पेश गर्नु पर्ने छ । केरमेट भएको दररेट मुल्यांकनमा समावेश गरिने छैन ।

(प्रमुख प्रशासकीय अधिकृत)
गेहेन्द्र बहादुर अधिकृत
प्रमुख प्रशासकीय अधिकृत



Tulsipur Sub - Metropolitan City
Office of the Municipal Executive

Tulsipur - Dang
Lumbini Province, Nepal

Bill Of Quantity (Boq)

तुलसीपुर, दाङ
लुम्बिनी प्रदेश, नेपाल
२०७३

मोहनराज बस्नेत
नगर प्रशासनिक अधिकृत

Name of Project :- Simalkanchi Road Gravel & Canal Construction
Location :- Tulsipur 11

S.N.	Description	Unit	Quantity	Rate (in figure)	Rate (In Words)	Amount
1	Earth work in excavation of foundation of structures in ordinary , including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. (Manual Means)	Cum	55.36			
2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (Old Norms)	Cum	20.75			
3	Providing and laying of PCC/RCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications including form works all complete. (2000)	Cum	38.34			
4	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS Clause 2014)	Kg	1389.54			



Tulsipur Sub - Metropolitan City

Office of the Municipal Executive

Tulsipur - Dang
Lumbini Province, Nepal

Bill Of Quantity (BOQ)

तुलसीपुर, डडेलधुर
लुम्बिनी प्रदेश, नेपाल
२०७३

Name of Project :- Simalkanchi Road Gravel & Canal Construction
Location :- Tulsipur 11

गेहेन्द्र बहादुर डाँगी
प्रमुख प्रशासकीय अधिकृत

S.N.	Description	Unit	Quantity	Rate (in figure)	Rate (in Words)	Amount
5	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:4 in structure including pointing works and providing necessary 100 mm dia HDPE pipes for weep holes etc all complete as per Drawing and Technical Specifications	Cum	6.12			
6	Construction of Hard Shoulder.(Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.)	Cum	113.40			
	Sub - Total					
	13 % VAT					
	Grand Total					