



तुलसीपुर उपमहानगरपालिका

नगर कार्यपालिकाको कार्यालय



पत्रसङ्ख्या :- ०१०/०१७

चलानी नं. :- ५३९५

तुलसीपुर, दाङ
लुम्बिनी प्रदेश, नेपाल

नगर कार्य २०७३
तुलसीपुर,
लुम्बिनी प्रदेश, नेपाल
२०७३

दररेट पेश गर्ने सम्बन्धि सूचना ।

प्रथम पटक सूचना प्रकाशित मिति २०८१/०२/२७

यस तुलसीपुर उपमहानगरपालिका द्वारा विभिन्न फर्म संग तपशिल बमोजिमको कार्य गर्नका लागि शिलबन्दी दररेट पेश गर्ने यो सूचना प्रकाशित गरिएको छ ।

सि. नं.	कामको विवरण	जम्मा रकम रु (मु.अ.क.बाहेक)	दररेट पेश गर्ने अन्तिम मिति	कैफियत
१	Ward No 18 Fencing Works (Tar Bar Works)	883619.19	2081-03-01	
२	Manikapur Pipal Chutara To Suvakoti Basic School Road Black Topped Works	883323.57	2081-03-01	

: दररेट पेश गर्ने फर्मले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोराको लिखित निवेदन सहित नबिकरण भएको फर्म दर्ता प्रमाणपत्रको प्रतिलिपी र आ.व.२०७९/०८० को करचुक्ता प्रमाणपत्रको प्रतिलिपी पेश गर्नु पर्ने छ ।

: दररेट पेश गर्ने फर्म तुलसीपुर उपमहानगरपालिका कार्यालयमा सुचिकृत हुनुपर्ने छ ।

: उक्त कार्यको लागि आवश्यक BOQ तुलसीपुर उपमहानगरपालिकाको वेबसाइट <http://www.tulsipurmun.gov.np> बाट डाउनलोड गर्न सकिने छ ।

: BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि लेखेर पेश गर्नु पर्ने छ । केरमेट भएको दररेट मुल्यांकनमा समावेश गरिने छैन ।

(प्रमुख प्रशासकीय अधिकृत)

गेहेन्द्र बहादुर डाँगी
प्रमुख प्रशासकीय अधिकृत



Tulsipur Sub-Metropolitan City
Office of the Municipal Executive

Tulsipur-Dang
Lumbini Province, Nepal
Bill of Quantity

Project Name : सडकपट्टा विप्लव चौतारा देखि शुभाकोटी गा.वि.जोड्ने सडक कालोपत्रे निर्माण ।
Location : Tulsipur- 18 dang
Contract No. :-

SN	Description Of Work	Unit	Quantity	Rate in NRs		Amount	Remarks
				In fig	In word		
A	Pavement Black Top Work						
1.00	Scarifying the existing road surface to a depth of 50mm and disposal of scarified materials with in all lifts and lead as per Drawing and technical specifications by mechanical means (Spec.cl.No: 1003)	Sqm	660.00				
2.00	Compacting original ground supporting sub-grade Loosening of the ground upto a level of 500mm below the sub-grade level ,watering, graded and compacted in layers as per drawing and technical specifications(Spec.cl.No: 1003/1005)	Cum	65.50				
3.00	Providing and laying granular sub-base on prepared surface ,mixing at OMC and compacting to achieve the desired density ,complete as per drawing and technical specifications by mechanical means(Spec. cl. No. 1201)	Cum	98.25				
4.00	Providing and laying crusher Run Macadam on a prepared surface, spreading and mixing, watering and compacting to form a layer of sub base course as per drawing and technical Specification (Spec.cl. No:1204)	Cum	65.50				
5.00	Providing and applying Prime Coat with hot bitumen(including cutter) of grade VG 10 on the prepared surface of granular base including cleaning of road surface and spraying at specified rate by mechanical means as per the Technical Specification.(Spec.cl. No: 1302)	Ltr.	655.00				
6.00	Providing and applying tack coat with hot paving grade VG 10 bitumin by mechanical means at specified rate on the prepared surfaces including cleaning as per technical specifications (Spec. cl. No: 1302)	Ltr.	360.25				
7.00	Providing and laying open-graded premix carpet of 20mm thickness composed of 13.2mm to 5.6mm aggregates as wearing course on apreviously prepared base as per drawing and technical specifications (Spec.cl.No:1311)	Cum	19.65				
8.00	Providing and laying seal coat sealing the voids in a bituminous surface as per drawing and technical specifications (Spec.cl.No:1310)	Sqm	655.00				
Total Amount (NRs.)							
VAT@ 13 % (NRs.)							
Grand Total (NRs.)							

Firm name:-

Authorize sign :-

Firm seal:-

Date :-



Tulsipur Sub-Metropolitan City
Office of the Municipal Executive

Tulsipur-Dang
Lumbini Province Dang

Bill of Quantity (BOQ)

Name Of Project : Ward Office Fencing Works.

Location : Tulsipur Sub-Metropolitan Word No . 18 Hemantapur Dang.

SN	Description Of Work	Units	Quantity	Rate in NRS		Amount	Remarks
				In fig	In word		
1.00	Site Clearance	Ls	1.00				
2.00	Earthwork in excavation of foundation on soft Soil	Cu.m	35.88				
3.00	Providing and laying boulder stone soling in foundation including voids packing with stone all acomplate as per instruction of the site incharge for wall foundation as per drawing,specification and instruction of site incharge.	Cu.m	7.18				
4.00	P.C.C. in(1:2:4) ratio for foundation & wall with approved quality of cement,sand & crushed stone aggregate including mixing,laying,curing, etc all complate as per the drawing,specification and instruction of site incharge.	Cu.m	12.56				
5.00	Stone Masonry Works 1:4	Cu.m	46.64				
6.00	Black Pipe post (50mm*50mm)	Kg	811.13				
7.00	Fencing Wire mesh Size 3''*3''	Sqm	348.50				
Total Amount (NRS.)							
VAT@ 13 % (NRS.)							
Grand Total (NRS.)							